



APPR. BY:  07/11
STEVEN C. NIX, CITY ENGINEER DATE

CITY OF CHINO HILLS
ENGINEERING DEPARTMENT

DATE	REVISION	BY

TRENCH BACKFILL
AND REPAIR

NOTES:

1. UNLESS SPECIFIED OTHERWISE, TRENCH CONSTRUCTION SHALL COMPLY WITH STANDARD SPECIFICATIONS FOR PUBLIC WORKS FOR CONSTRUCTION ("GREEN BOOK"), LATEST EDITION.
2. TRENCH OPENINGS SHALL BE BACKFILLED AND CONSOLIDATED PER "GREEN BOOK", LATEST EDITION.
3. WHEN TWO OR MORE TRENCH OPENINGS ARE LESS THAN 5 FEET APART OR LESS THAN 4 FEET FROM EDGE OF AC PAVEMENT, THE EXISTING BASE PAVEMENT SHALL BE REPLACED BETWEEN EXCAVATIONS OR EDGE OF GUTTER LIP.
4. IF EXCAVATIONS FOR LATERAL CROSSINGS ARE LESS THAN 50 FEET APART, FINISH SURFACE PAVEMENT SHALL BE CONTINUOUS BETWEEN EXCAVATIONS.
5. UNLESS OTHERWISE INSTRUCTED BY THE CITY ENGINEER, TRENCH PATCH SHALL BE STRAIGHT GRADE ACROSS WIDTH AND SHALL NOT BE CROWNED AT CENTER.
6. TACK COAT SHALL BE APPLIED UPON THE EXISTING SURFACES PRECEEDING THE PLACEMENT OF THE ASPHALT CONCRETE.
7. ALL TRAFFIC STRIPING AND MARKINGS THAT ARE REMOVED OR DISTURBED SHALL BE REPLACED IN KIND OR AS DIRECTED BY THE CITY ENGINEER.

APPR. BY:  07/11 STEVEN C. NIX, CITY ENGINEER DATE			CITY OF CHINO HILLS ENGINEERING DEPARTMENT	
DATE	REVISION	BY	TRENCH BACKFILL AND REPAIR	
			118 2 of 2	